



MARYLAND SERIAL NO.: 8237-86

APPROVED  
**RADCO**  
 May 07, 2020

**COLUMN STRAPPING SCHEDULE:**

(A) (2) 2x4 SPF #2 THIS HALF.	(B) (2) 2x4 SPF #2 EACH HALF
(C) (3) 2x4 SPF #2 THIS HALF.	(D) (3) 2x4 SPF #2 EACH HALF.
(E) (4) 2x4 SPF #2 THIS HALF.	(F) (4) 2x4 SPF #2 EACH HALF.
(G) (3) 2x6 SPF #2 THIS HALF.	(H) (3) 2x6 SPF #2 EACH HALF.

NOTES:  
 1. ALL COLUMN STUDS SHALL BE GLUE/NAILED TOGETHER.  
 PVA GLUE WITH 100% COVERAGE SHALL BE USED.  
 2. INSTALL TWO STEEL STRAPS AT EACH STUD OF EACH COLUMN.  
 3. COLUMN STUDS SHALL NOT BE NOTCHED OR BORED.

CONSULTING ENGINEER: WALTER E. MOOD, P.E. - 186 W. LONGLEAF DR. - SYLVESTER, GA. 31781

--	--	--	--

**SPECIALIZED STRUCTURES INC.**  
 2402 SPRINGGATE OGDON ROAD WILACODONNE, GA 31602  
 1-912-384-7825 FAX: 1-912-384-4942

DATE: 4-18-20	THIRD PARTY: RADCO
SCALE: 1/4"=1'-0"	ONE INCHMAN COVER SHEET 102
COORDS: SEE NOTES	TAMPA, FLORIDA 33624
STATE/NO. VA. A/L NO.	REVISIONS:
REFERENCE: 8237	BY: W.E.W.
SS15637-86 A/B	SHEET
23'-4" x 34'-0" EDUCATION	2 OF 7
FLOOR PLAN	DESIGNER/ISS. DATE NO. 22 05/07/20